Sl. No.	Particulars	Quantity	Per	Rate	Cost
				Rs. a. p.	Rs.
7	Cement pointing with thread lines	207 or 2·07	Sqr.	3 0 0	
8	White and colour washing, two coats as per plastering and pointing	44·64	,,	0 4 6	
9	Roofing with First class Mangalore tiles on T.W. reepers 2″×1″ including wood oiling and tying the tiles to double reepers with galvanized wire	1,485 or 15·00	S.ft. Sqr.	25 0 0	
10	Ridge tiles set in mortar and cement pointed complete	78	R.ft.	0 8 0	
11	Ventilating tiles big size, fixing, etc., complete	16	Nos.	2 8 0	
12	T.W. work wrought and put up including two coats of wood oiling	65·13	C.ft.	4 8 0	
13	T.W. doors battened 1″ thick shutters with all fixtures complete (frames 3″×4″) and flat iron clamp 1′ long and 2′ wide	156	S.ft.	1 2 0	
14	T.W. battened windows 1″ thick shutters and $\frac{5}{8}$″ dia. iron bars with all fixtures complete	75	,,	1 6 0	
15	T.W. shelves with frames, shutters and shelf planks, etc., complete	60	,,	1 0 0	
16	Chocolate painting, two coats, doors both sides	7·52	Sqr.	4 8 0	
17	Constructing sinks in bath rooms	4	Nos.	5 0 0	
18	Providing stone mortar and pestle fixed complete	4	,,	5 0 0	
19	Flooring with 3″ lime concrete (1 : 3) and $1\frac{1}{2}$″ cement concrete (1 : 2 : 4) on top with $\frac{1}{2}$″ cement plastering (1 : 3) on top complete with red ochre colour	541 or 5·5	Sqr.	25 0 0	
	(*a*) Do without red ochre colour	249 or 2·5	,,	23 0 0	
20	Levelling ground, etc.	1	Item		
21	Electric lighting and water supply	1	,,		
22	Providing and fixing T.W. planks with T.W. pegs, etc., complete	100	S.ft.	0 8 0	
23	Constructing "V" shaped drain 4″ in lime concrete as per specification	70	R.ft.	0 4 0	
24	Chunam patty brick in lime mortar 3″×6″ plastered, etc., complete	125	S.ft.	0 4 0	
25	Excavating soakage pits 5′×5′×6′ and filled with brick bats of $1\frac{1}{2}$″ to 2″ size well burnt and connecting the drain to it with a galvanized pipe 3″ to 4″ dia. and an iron grating at the entrance, etc., complete		L. S.		6
26	Fencing alround		,,		144
27	Constructing latrine		,,		200

B. S. NARASINGA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 23rd February 1940.

The attention of the public is drawn to the notification calling for tenders for "constructing an Intermediate College at Shimoga" published in pages 438-441, Part VI of the *Mysore Gazette*, dated 29th February 1940.

Tenders will be received by the Executive Engineer, Shimoga Division, up to 3 P.M. on 18th March 1940.

Earnest money required for the work is Rs. 6,775 which should be credited to the Treasury to "17 (*a*) P. W. Deposits" and challan enclosed.

Abstract Notification dated 2nd March 1940.

The attention of the public is drawn to the notification calling for tenders for restoring Dorligodu Minor tank, Reg. No. 570 of Hiresara village, Tirthahally Taluk, published on pages 490-491, Part VI of the *Mysore Gazette*, dated 7th March 1940.

Tenders will be received by the Executive Engineer, Shimoga Division, up to 3 P.M. on Monday the 25th March 1940.

Earnest money required for the work is Rs. 90 which should be credited to the Treasury to "17 (*a*) P. W. Deposits" and challan enclosed.

Notification dated 8th March 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M., on 30th March 1940, for improving Bhadravati-Holehonnur Road from 4 to 6 miles. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1941.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four for each form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury chellan for Rs. 360, credited to "17 (a) P.W. deposits" as earnest money, and be superscribed "Tender for improving Bhadravati-Holehonnur road from 4 to 6 miles," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for the area.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards security deposit.

Abstract estimate for improving Bhadravati-Holehonnur Road, 4–6 miles.

Sl. No.	Items of work	Unit	Rate	Quantity
			Rs. a. p.	
1	Jungle clearing including cutting and removing trees ..	Fug.	5 0 0	22
2	Rooting out tufty grass	Sqr.	0 3 0	1,624
3	Picking and forming	,,	0 1 0	2,376
4	Earthwork excavation in mixed soils for cutting sides and forming	C.yd.	0 3 0	1,407
5	Earthwork excavation of side drains	,,	0 2 6	1,540

Sl. No.	Items of work	Unit	Rate	Quantity
			Rs. a. p.	
6	Earthwork excavation of check drains in mixed soils and using earth for forming road	C.yd.	0 3 0	4540
7	Earthwork excavation and filling for scours and ruts with consolidation	,,	0 2 6	..
8	Earthwork banking with watering and consolidation ..	,,	0 4 0	10,881
9	Removing hard rock by blasting	,,	2 12 0	38
10	Constructing pipe tunnels	Details will be published later on.		
11	Constructing masonry tunnels ..			
12	(*a*) Constructing masonry culverts			
	(*b*) Constructing culvert at 1/6 ..			
13	Improving the existing culvert at 6/10			
14	Rough stone boulder filling	C.yd.	1 8 0	..
15	Collecting and stacking gravel with half mile lead ..	,,	0 8 0	2347
16	Spreading and forming and consolidation of gravel ..	,,	0 4 0	2347
17	Supplying and fixing mile stones	No.	10 0 0	3
18	Do furlong stones	Each	3 0 0	21
19	Do demarcation stones	,,	1 0 0	96
20	Do sign post in R.C.C.	,,	50 0 0	..
21	Supplying steam road roller	,,	100 0 0	1
22	Forming approaches to Ragekodamaggi halla and Hulibasappanahalla	,,	250 0 0	1

Notification dated 8th March 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M., on 30th March 1940, for improving Bhadravati-Holehonnur Road 7 to 4/11 miles. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1941.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas 4 for each form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury chellan for Rs. 600 credited to "17 (*a*) P. W. deposits" as earnest money, and be superscribed "Tender for improving Bhadravati-Holehonnur Road 7 to 4/11 miles" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards the security deposit.

Abstract estimate for improving Bhadravati-Holehonnur Road, 7—4/11 miles.

Sl. No.	Items of work	Unit	Rate	Quantity
			Rs. a. p.	
1	Jungle clearing including cutting and removing trees ..	Fug.	5 0 0	14
2	Rooting out tufty grass	Sqr.	0 3 0	2072
3	Picking and forming	,,	0 1 0	3564
4	Earthwork excavation in mixed soils for cutting sides and forming	C.yd.	0 3 0	417
5	Earthwork excavation of side drains	,,	0 2 6	2567
6	Earthwork excavation of check drains in mixed soils and using earth for forming road	,,	0 3 0	7920
7	Earthwork excavation and filling for scours and ruts with consolidation	,,	0 2 6	2362
8	Earthwork banking with watering and consolidation ..	,,	0 4 0	15628
9	Removing hard rock by blasting	,,	2 12 0	34
10	Constructing pipe tunnels	Details will be published later on.		
11	Constructing masonry tunnels ..			
12	(*a*) Constructing masonry culverts ..			
	(*b*) Constructing culvert at 1/6 ..			
13	Improving the existing culvert at 6/10			
14	Rough stone boulder filling	C.yd.	1 8 0	1100
15	Collecting and stacking gravel with half mile lead ..	,,	0 8 0	3422
16	Spreading and forming and consolidation of gravel ..	,,	0 4 0	3422
17	Supplying and fixing mile stones	No.	10 0 0	4
18	Do furlong stones	Each	3 0 0	32
19	Do demarcation stones	,,	1 0 0	144
20	Do Sign post in R.C.C.	,,	50 0 0	1
21	Supplying steam road roller	,,	100 0 0	1
22	Forming approaches to Ragekodamaggi halla and Hulibasappanahalla	,,	250 0 0	1

W. A. HUKERI,
Executive Engineer.

ANJANAPUR DIVISION.

Abstract Notification dated 23rd February 1940.

The attention of the public is drawn to the Notification calling for tenders for constructing a Circle 100 feet diameter at entrance to waste weir of Anjanapur Reservoir, Shikaripur Taluk, published on pages 441-442, Part VI of the *Mysore Gazette*, dated 29th February 1940.

2. The tenders will be received by the Executive Engineer upto 12 NOON on 1st April 1940.

3. The earnest money required for the work is Rs. 140 which should be credited to the Treasury to "17. (*a*) P. W. Deposits" and the relative chellan enclosed.

M. V. KRISHNASWAMY IYENGAR,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 26th February 1940.

The attention of the public is invited to the Notification, published on pages 492-498, of Part VI of the *Mysore Gazette*, dated 7th March 1940 calling for tenders for the work of constructing Dispensary Buildings at Bukkambudi, Tarikere Taluk.

The last date of receipt of tender in this office is 16th March 1940.

M. A. RAMANUJAM,
Executive Engineer.